ABSTRACT.

For extending and improving Engine House at Soldevanhalli Pumping Station for electrification.

No.	Items of work	Per	Quantity
1	Dismantling old wall and throwing rubbish far off	C. ft.	1913
2	Removing and refitting corrogated zinc sheet roofing	Sqr.	7'44
3	Earthwork excavating foundation and filling basement including consolidation	C. yd.	69
4	Earthwork for insufficient in filling basement	Lump sum Rs.	
5	Chunam concrete	C. ft.	1296
6	Burnt stone in chunam for filling foundation	,,	1182
7	Do for superstructure	,,	3139
8	Old burnt stone in chunam	,,	1275
9	Burnt stone slabs 6" thick dressed	Sq. ft	110
10	Burnt stone in chunam arch work	C. ft.	209
11	Pointing with cement	Sqr.	35'27
12	Burnt brick in chunam	C. ft.	272
13	Plastering with chunam	Sqr.	39'67
14	Roofing with corrogated zinc sheet with all its requisites, etc., complete ..	,,	15'81
15	Corrogated ridging with ornamental cresting, etc., complete	R. ft.	51
16	Flooring with Mangalore tiles on 6" concrete bed	Sqr.	19'80
17	Teakwood door pannelled shutters with iron clamps, etc., complete	Sq. ft.	80
18	Teakwood windows with pannelled shutter outside and glazed inside with iron clamps, etc., complete	,,	168
19	Semi-circular fan lights over door and windows, complete	,,	69
20	Teakwood work wrought and put up including painting, etc., complete ...	C. ft.	325
21	Holding bolts to crane sleepers with nuts, washers, etc., complete, (rod 3" length and 1" diameter.)	Each	66
22	Drilling holes in existing wall to insert above bolts	,,	40
23	Ornamental teak eave board	R. ft.	106
24	Removing and fixing old eave board	,,	52
25	Silicate painting	Sq.	16'04
26	Removing and refixing old circular ventilator	Each	1

JOHN BHORE,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notificatian published in the *Mysore Gazette*, dated the 28th September 1916, pages 735 and 736, Part IV, calling for tenders to construct "New Public Offices in the Cenotaph Road, Bangalore."

Dated 2nd October 1916.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 1 P.M. of the 16th October 1916, for Improving Sandal Koti building, Fort, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty (Rs. 250) in cash, as earnest money, and be superscribed "Tender for improving Sandal Koti building, Fort, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for Improving Sandal Koti building, Fort, Bangalore.

No.	Items of work	Per	Quantity
1	Removing the roof including Arcot flat tiles, reepers, couple, rafters, etc., complete.	Sq.	56·84
2	Roofing with Mangalore tiles on teak reepers with plastering underneath, etc., complete.	,,	56·84
3	Teakwood work wrought and put up	C. ft.	407
4	Providing wall plate of stone slabs on top of wall	S. ft.	576
5	Dismantling top of wall and rebuilding with brick in chunam ...	C. ft.	570
6	Brick in chunam cornice work 9" × 9" alround	R. ft.	386
7	Fixing old Mangalore ridge tiles, set in mortar including cement pointing	,,	81
8	Do new do do	,,	132
9	Repairing cracks in walls and patch repairs	L. S.	
10	White and colourwashing and sundry works, repairs to doors and windows ...	,,	
11	Flooring with burnt stone slabs roughly dressed on 3" concrete and cement pointing.	Sq.	70·72
12	Flooring with Cudappah slabs or Mangalore tiles on 3" concrete and cement pointing.	,,	6·97
13	Putting zinc sheets 3 feet wide for valleys with ½" teakwood planks and chunam borders, etc., complete.	R. ft.	92
14	Wood oiling to teakwood work	Sq.	23·00
15	Burnt stone upright slabs 4½" thick, roughly dressed alround walls for a height of 4 feet from floor level including chunam pointing.	,,	30·00

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice dated 18th September 1916.

Notice is hereby given that sealed tenders will be received at the office of the Sub-Division, Chikballapur, Kolar District, up to 5 P.M. of 28th October 1916, for improving the Prakarams of Sri Bhoga Nandiswaraswami temple at Nandi, Chikballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the office of the Sub-Division, Chikballapur, between the hours 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Sub-Division Officer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (rupees three hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Prakarams of Sri Bhoga Nandiswaraswami temple at Nandi, Chikballapur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Sub-Division Officer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tenders, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Sub-Division Officer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
1	Earthwork excavating, foundation and filling in	C. yd.	162
2	Burnt stone in mud	C. ft.	4,864
3	Burnt brick in mud	,,	19,797
4	Chunam plastering	Sq.	219·67
5	Mud plastering	,,	223·29
6	Honnewood battened door with hinges, bolts and iron clamps, etc. ...	S. ft.	702
7	Honnewood battened windows with hinges, bolts, hooks, iron clamps and iron bars, etc.	,,	350
8	Chocolate painting (2 coats)	Sq.	21·04
9	Burnt stone slabs, dressed, including lifting	S. ft.	1,098
10	Cut stone work	C. ft.	240
11	Concrete in chunam with plastering to the roof of ankanams	Sq.	43·21
12	Unforeseen items including constructing one drain, removing ant hills and dismantling old walls, etc.	Lump	sum.
13	Gravelling the floor with consolidation and cow dung wash, including one mile lead for gravel.	Sq.	135·67
14	Overhauling the dilapidated ankanams—		
	(a) Removing and relaying stone work.	C. ft.	624
	(b) Removing the existing concrete above the roof	Sq.	3·24
	(c) Putting fresh chunam concrete with plastering over the roof ...	,,	3·24
15	Bringing displaced pillar beams to normal position	Lump	sum.
16	White and colourwashing	Sq.	442·86

M. G. KRISHNASWAMI RAO,
Sub-Division Officer, Chikballapur.